PROPOSED CHANGE ORDER | PCO-001

RTU-1 curb support repair (concealed roof deck condition)

Project:	Sample Elementary School HVAC Replacement (Sample ISD)
Reference:	RFI-001; Sample Engineering, Inc. repair detail
Project #:	2026-0001
Owner:	Sample ISD
Engineer:	Sample Engineering, Inc. (Alex Poe, PE)
Contractor:	Example Mechanical, LLC
Date:	March 2, 2026

Amount:	**$10,000.00, firm.** The Engineer directed repair of a concealed roof deck condition at RTU-1.
Schedule:	Holding the contract completion date. No added time requested now (Section 4).
Funding:	Owner Contingency ([clause]). Pays after the signed Change Order.

1. WHAT WE FOUND

- We opened the roof at RTU-1 and found no metal deck under one side of the curb. Not shown on the plans.
- We stopped, left it as found, and sent RFI-001. Concealed condition ([clause]). Notice first.

2. THE FIX (Engineer directed)

- Sample Engineering, Inc. (Alex Poe, PE) issued the detail: weld steel angle supports (L3x3x1/4), add new 22 gauge deck, reset the curb, reroof to match.

3. COST (broken out)

A. Subcontractor and vendor work	
A1. Steel angle and new metal deck (welder subcontractor), itemized in the attachment	$2,500.00
A2. Reroof the area opened for the fix (roofer subcontractor), itemized in the attachment	$4,000.00
A3. Crane, added pick for the repair (vendor estimate)	$1,000.00
Subtotal A	**$7,500.00**
B. Contractor field labor (rates in the itemization)	
B1. Working Foreman 10 hr and Working Tech 10 hr: rig and assist the weld and set the deck	$1,750.00
B2. Working Tech 6 hr and protection material: protect the space below during hot work	$750.00
Subtotal B	**$2,500.00**
TOTAL (firm)	**$10,000.00**

Each A line is that firm's own price. The welder and roofer are broken out in the attachment.

4. SCHEDULE

- We cannot set the unit until the deck is fixed. We hold the completion date and will add crews if needed.
- We reserve added time only if the condition or abnormal weather still affects the date ([clause]).

5. NOTES

- Concealed condition ([clause]): notice given, not disturbed.
- Reserved, only if incurred with backup: added cost to hold the date, or deck repair beyond the area shown.

SIGN OFFS (all three sign before the changed work is billed)

Contractor: Example Mechanical, LLC

_____ Date: _____

Pat Doe, Project Manager

Engineer: Sample Engineering, Inc.

_____ Date: _____

Alex Poe, PE [ ] Approve [ ] Approve as noted [ ] Reject

Owner: Sample ISD

_____ Date: _____

Sam Roe, Owner Representative

6. ATTACHED

- Itemization. Engineer's detail. RFI-001. Welder proposal. Roofer proposal. Crane estimate.

Scope and Cost Itemization (broken out)

Every trade broken out: description, quantity, unit cost, total, and labor by hours and rate

Sample Elementary School | PCO-001 (RTU-1) | Example Mechanical, LLC. Subcontractor and vendor lines are each firm's own price. Labor rates: working foreman $100.00 per hour, working tech $75.00 per hour.

Section A1. Welder subcontractor: firm $2,500.00

Subcontractor firm lump. The table allocates the price into the Engineer's format: materials by item with quantity and unit cost, labor as men times hours times rate, trip on its own line.

Welder materials (itemized)

Item	Qty	Unit cost	Total
Steel angle, L3x3x1/4	10 LF	$20.00	$200.00
Metal deck, 22 gauge	50 SF	$10.00	$500.00
Gas, fasteners, misc	1 LS	$100.00	$100.00
Materials subtotal			**$800.00**

Welder labor (men times hours times rate)

Crew	Men	Hours	Rate	Total
Welders: cut and weld the angle supports and set the deck	2	8.0	$100.00	$1,600.00
Labor subtotal				**$1,600.00**
Materials				$800.00
Labor				$1,600.00
Trip charge				$100.00
Welder total (firm lump, subcontractor proposal)				**$2,500.00**

Section A2. Roofer subcontractor: firm $4,000.00

Pass through at the roofer's firm price. Every line foots to the total. Scope: remove the opened area down to the deck, replace insulation and cover board, and reroof to match so the roof warranty holds.

Roofer cost, itemized (roofer proposal)

Line	Type	Amount
Insulation and cover board	material	$500.00
Membrane and flashing	material	$500.00
Kettle and equipment	equipment	$500.00
Labor and installation	labor	$2,000.00
Overhead, profit, and insurance	markup	$500.00
	Firm total (roofer cost)	**$4,000.00**

Section A3. Crane, vendor: $1,000.00

Vendor price from the crane estimate for the added pick. Trues to the actual invoice. Estimate attached.

Section B. Contractor field labor, by role

Item	Task	Frmn hr	Tech hr	Labor	Matl	Total
C1	Working Foreman: rig and assist the weld, set the new metal deck, and reset the curb.	10	0	$1,000.00	$0.00	$1,000.00
C2	Working Tech: support the welder, hand material, control the area, clean up.	0	10	$750.00	$0.00	$750.00
C3	Working Tech: protect the space below during hot work; protection material.	0	6	$450.00	$300.00	$750.00
	Subtotal, Example Mechanical labor	**10**	**16**	**$2,200.00**	**$300.00**	**$2,500.00**

Labor priced at the rates shown at the top of this itemization.

Totals

Line	Type	Amount
A1. Welder subcontractor, firm	subcontract	$2,500.00
A2. Roofer subcontractor, firm	subcontract	$4,000.00
A3. Crane, vendor	vendor	$1,000.00
B. Contractor field labor	labor	$2,500.00
	TOTAL (firm)	**$10,000.00**